

## Werksprüfbescheinigung

WPZ 023

### Roof system part:

■ Wakaflex/ Abutment material

The product qualities (statement):

Fire behavior of building-materials and parts of a building; DIN 4102 part 1; Examination by FMPA Stuttgart; Examining testimonial 1678877	B2 i.e. normally inflammable
Fire behavior of building-materials and parts of a building; DIN 4102 part 7; Examination by FMPA Stuttgart; Examining testimonial 1697039	Test on resistance against flight- and radiant warmth fires more unrestrictedly slope of the roof passed
Xeno test: Examination by SKZ seasoning castle; Test report: 31111/95	no formation of bubbles no color changes
Warmth stability: Examination MPA Darmstadt; Test report K 91 280	at 200 C: slip neither ascertainable still changes
Bend test: Examination by SKZ seasoning castle; Report 28441/94	at -20 C to +80 C break still tore neither
physiological Unbedenklichkeit; (examination by Hy- gieneinstitut university of Heidelberg report: 28.05.91)	physiologically quite safe
Weather resistance (QUV-Bewitterung/dewfall) and Freibewitterung in the company experiment area	Long time requests you fulfill

The high quality standards of our roof system parts are supervised strictly in company laboratories. Neutral, independent and international recognized institutes certify not only the product quality to much of processes and method dictated to our article but also the retention at the production location.

We make sure therefore that our products and services correspond to the highest internationally comparable quality requirements.

Version: 6-1-2001

Ersteller: R. Simon

Release:

Qualitätsmanagement

Qualitätsprüfung

