

Work examining certificate

WPZ 018

Roof system part:

- PVC valley (without supporting metal)

The product qualities, (statement):

Fire behavior of building-materials and parts of a building; DIN 4102 part 1	Building-material class B2 Test report K 83 181.2 MPA Darmstadt
Tensile strength after DIN 53 455, version 08/81 Rehearsing body form: Norm stick S2 after DINs 53 504 Breaking stretching	≥ 24 [N/mm ²] ≥ 280 [%] Test report K 83 181.2 MPA Darmstadt To xenon test Bewitterung (1500 H) none of significant changes ascertainable
Harden to Shore A: Examining execution after DIN 53505, version June, ' 87	□ 87
Weather resistance (QUV-Bewitterung/dewfall) -and Freibewitterung in the company test area	Long time requests are fulfilled

The high quality standards of our roof system parts are supervised strictly in company laboratories. Neutral, independent and international recognized institutes certify not only the product quality to much of processes and method dictated to our article but also the retention at the production location.

We make sure therefore that our products and services correspond to the highest internationally comparable quality requirements.

Version: 6-1-2001

Ersteller: R. Simon

Release:

Qualitätsmanagement

Qualitätsprüfung

